

# Technical specifications

## **Data Center Arezzo (IT1)**

## RATING 4 CERTIFIED MAXIMUM RELIABILITY

#### General

Total surface area: 5.000 m<sup>2</sup> Data hall net surface area: 1.500 m<sup>2</sup>

- ✓ Secure location in terms of earthquakes
- √ Secure location in terms of hydro-geological risks

#### Structure

Usable height of the data hall: 3 m

#### **Certifications and compliance**

- ✓ ANSI/TIA 942-A Rating 4 (formerly Tier 4)
- √ GO Guarantee of Energy Origin (100% renewable)
- √ ISO 9001 Quality of services offered
- √ ISO 27001 IT security
- ✓ ISO 50001 Energy management system
- ✓ ISO/IEC 27017 Cloud security controls
- √ ISO/IEC 27018 Managing personal data on the Cloud
- ✓ ISO/IEC 27035 Managing security incidents and events

#### Services

Colocation solutions: rack portions; dedicated racks Power per rack: up to 40kW

- √ 24h Smart hands & eyes
- √ 24h Systems management

### Connectivity

Point of entrance: 4 Entrance Room: 2

Main Distribution Area (MDA): 2

- √ Carrier neutral data center
- √ Provision of managed connectivity
- ✓ Ultra-redundant connection with (IT2) via multi-fiber cables, running along two different routes

## Energy

Total power: 4MW (redundant) UPS redundancy: 2 N+1

UPS type: double conversion static Individual UPS power: 500kVA

UPS run time: 30 minutes (standard) - 15 minutes (minimum)

Generator redundancy: 2N

Generator type: diesel generator units Full load run time: 48h without refueling

### Cooling

Dual cooling system: chilled water + gas direct expansion with Dynamic Free Cooling

Cooling system redundancy: 2N

#### Sicurity

- ✓ CCTV
- √ Separate parking for employees/visitors
- √ 24/7/365 security
- √ Network Operations Center (NOC) 24/7/365
- √ Building Management System (BMS)

#### Fire prevention

Air replacement: integrated in DFC system Extinguishing system: inert gas Extinguishing gas: IG-100

- √ Highly sensitive smoke detection system
- ✓ Underfloor liquid loss detection system





## **Data Center Arezzo (IT1)**

Via Gobetti, 96 - 52100 Arezzo

## Main nearby airports

Florence (FLR): 1 h Rome (FCO): 2h 15 min

## **Nearby railway stations**

Arezzo: 10 min Florence: 1 h

## **Nearby motorway tollbooths**

Carrara Massa

Lucca

Pisa

Livorno

Arezzo (A1): 10 min

Estimated average time by car.



FIUMICINO

